

MAKING MODERN LIVING POSSIBLE

Danfoss



VLT® AQUA Drive

The ultimate solution for Water, Wastewater & Irrigation

VLT®
THE REAL DRIVE

The VLT® AQUA Drive is innovative

– Reduces system, installation and operating costs



Danfoss VLT® AQUA Drive is dedicated to water and wastewater applications. With a wide range of powerful standard and optional features, the VLT® AQUA Drive provides the lowest overall cost of ownership for water and wastewater applications.

Save energy

The VLT® AQUA Drive offers considerable energy savings:

- VLT® efficiency (up to 98%)
- Sleep Mode
- Automatic Energy Optimisation AEO: Typically 3-5% energy saving
- Flow compensation, lowering pressure set point and thus energy consumption under low flow conditions

Save space

The compact design of the VLT® AQUA Drive makes it easily fit in even small installation spaces.

- Built-in DC coils for harmonic suppression. No need for external AC coils
- Optional, built-in RFI filters in the whole power range
- Intelligent cooling concept reduces need for installation space.

Protects the environment

The growing need for clean water and energy conservation is rapidly increasing the pressure on global fresh water resources, wastewater treatment, recycling and power generation. VLT® AQUA Drive is designed to enhance system operation, protect equipment, reduce chemical consumption and water loss, while providing significant energy savings. VLT® AQUA Drive is the ultimate solution for all water, wastewater and recycling processes.

Save cost and protect your system

with a series of pump-specific features:

- Cascade controller
- Dry run detection
- End of curve detection
- Motor alternation

- 2-step ramps (initial and final ramp)
- Check valve protection
- Safe stop
- Low flow detection
- Pipe fill mode
- Sleep mode
- Real-time clock
- Password protection
- Overload trip protection
- Smart Logic Controller

Can be set to either variable or constant torque operation in the full speed range.

Save panel space

NEMA/UL Type 12 (IP 54/55) enclosure solution is available in the whole power range.

Up to 90 kW, the VLT® AQUA Drive can even be delivered in an IP 66 version.

Save time

VLT® AQUA Drive is designed with the installer and operator in mind in order to save time on installation, commissioning and maintenance.

- Intuitive user interface with the award-winning control panel (LCP)
- Same user interface for the full power range
- Modular VLT® design enables fast installation of options
- Auto tuning of PI controllers
- Robust design and efficient monitoring make the VLT® AQUA Drive maintenance free.


Dedicated to water and wastewater

Danfoss Drives' unequalled experience was used to make the VLT® AQUA Drive the perfect match for AC motor driven applications in modern water and wastewater systems – also for retrofitting.

Water and Wastewater is a global business area for Danfoss Drives and you will find our dedicated sales and service staff all over the world 24 hours a day.




Ideal Energy Consumption at Varying Speed



Energy savings using a VLT® AQUA Drive are achieved even with a modest reduction in speed.


Distribution System Water Losses



Reducing water losses by lowering system pressure becomes increasingly effective as the size of line breaks increase.

Water and Wastewater processes

– Improved control using less energy



1 Water treatment plants

Meeting the varying flow demands on a daily or hourly basis requires reliable control. The VLT® AQUA Drive software provides unique pump control features that will help control even the most demanding applications.

2 Desalination plants

Desalination plants are used to provide clean drinking water from sea water or brackish water. In desalination plants saline environments often requires good

protection against corrosion. The optional high grade PCB coating and a mechanical design, which separates the electronics from the cooling air, makes the VLT® AQUA Drive the perfect solution for this application.


3 Groundwater pumps

Submersible deep well pumps need fast start and stop capability, precise control and protection against running dry. The built-in dry run detection and the initial and final ramp ramps make the

VLT® AQUA Drive handle such applications to perfection.

4 Wastewater plants

Fluctuations in flow can disrupt efficient process control, increase costs and equipment wear due to a higher number of starts and stops, and adversely affect effluent quality. Using the VLT® AQUA Drive on pumps, blowers and other equipment will lead to better process control and reduce energy consumption. The VLT® AQUA Drive can also provide



tighter control of chemical feed pumps, mixers and other equipment.

5 Irrigation systems

The irrigation market is focusing more and more on efficiency and energy savings for water management. Meeting these demands requires precise pressure and flow control. The built-in pump control features makes VLT® AQUA Drive a perfect match for irrigation in rural areas. It even offers a special pipe fill function that prevents water

hammering and reduces leakage when empty pipes are filled.

6 Distribution

As areas become more populated, the increasing demand for reliable and precise pressure control becomes a challenge to many communities. The VLT® AQUA Drive has innovative pumping functions to assist in maintaining precise pressure and flow while reducing system leakage and energy consumption. In many cases, it can also provide a

cost-effective alternative to water towers. The Cascade Controller has advanced distribution functions built-in.

7 Water fountains and pools

Water fountains are used to enhance the aesthetics of buildings and parks nearly everywhere. In these applications, the VLT® AQUA Drive can provide energy efficiency, accurate control and even meticulously timed sequencing for a dramatic effect.

The modular VLT® AQUA Drive

Extremely compact panel mount cabinets



C3 – frame IP 20 compact panel mounting drive.



Mains and motor cable terminals are located in the bottom of the cabinet for fast and easy installation.

The IP 20 enclosure has two individually controlled fans for maximum reliability.

Only a minimum of external cooling air passes the electronic components, which increases the lifetime.

The aluminium front hinged door ensures easy access to additional I/O options and control wiring.

IP 21/Type 1 protection can be delivered as a kit solution or as a specific IP 21 drive with easy access plastic cover with snap locks.

Extremely robust cabinets for harsh environments



The Danfoss IP 55/NEMA 12 or IP 66 are designed for use in harsh environments with gas, pollution and dust. The electronics are completely separated from the cooling air in order to increase the lifetime.

All terminals and EMC connections are located inside the drive under the robust metal cover for maximum protection.

If ordered as IP 66 the heat sink is protected against corrosion (IP 66 rating is available up to 90 kW).

1 Fieldbus option

- Modbus RTU (std.)
- Modbus TCP IP
- PROFIBUS
- DeviceNet
- EtherNet/IP
- PROFINET

2 Local Control Panel (LCP)

Choose numerical, graphical or no display

3 I/O option

- General Purpose I/O (3DI + 2AI + 2DO + 1AO)
- Cascade controller (2 – 8 pumps)
- Sensor input (3 x PT100/1000 + 1AI)
- Relay output (3 x relays)

4 24 V supply option

5 RFI filter

Built-in RFI Filter for long motor cables according to the IEC 61800-3 and EN 55011 standards.

6 AC mains disconnect

(Factory mounted option)

7 Input mains option

Various input plate configurations are available including fuses, mains switch (disconnect), or RFI filter. Input plates are field adaptable if options need to be added after installation.

8 Coated PCB's

Durable in aggressive environments

In water and wastewater applications it is often recommended to protect the drive with coated PCB's. As standard the VLT® AQUA Drive complies with level 3C2 according to IEC 60721-3-3. Protection level 3C3 is optionally delivered from factory.

The option protects significantly better against chlorine, hydrogen sulphide, ammonia and other gasses.

9 Unique cooling concept

- No ambient air flow over electronics up to 90 kW
- Above 90 kW designed with back channel cooling (85% heat dissipated via back channel)

10 Advanced cascade controller option

Controls up to 9 pumps

VLT® quality up to 1.4 MW


The VLT® AQUA Drive is available from 0.25 kW to 1.4 MW.

Drive experience since 1968 lies behind the clever design of VLT® drives. All enclosures are mechanically designed with focus on:

- Robustness
- Easy access and installation
- Intelligent cooling
- High ambient temperatures
- Long service life

All VLT® AQUA Drives share technology, user interface and basic features with the rest of the new VLT® generation to assure well documented and proven quality.

The modular design of the VLT® AQUA Drive allows even highly customised drives to be mass produced and factory tested.




Remote access via fieldbus and USB cable. VLT® Set up Software MCT 10 gives intuitive access to all parameters and has scope features with graphs showing feedback, current, frequency etc. for easy fault finding and documentation.

DC coils reduce harmonic noise and protect the drive. Also EMC filters are integrated (meets EN 55011 A2, A1 or B).




Dedicated water features



Auto tuning of the PI controllers

With auto tuning of the PI controllers, the drive monitors how the system reacts on corrections made by the drive – and learns from it, so that precise and stable operation is achieved quickly.

Gain factors for PI are continuously changed to compensate for changing characteristics of the loads. This applies to each PI controller in the 4-menu sets individually. Exact P and I settings at start-up will not be necessary – which lowers the commissioning costs.




Pipe Fill Mode

Enables controlled (closed loop) filling of pipes.

Prevents water hammering, bursting water pipes or blowing off sprinkler heads.

The new pipe fill mode is usable in both vertical and horizontal pipe systems.


Useful in all applications where controlled pipe filling is demanded, such as irrigation systems, water supply systems, etc.



End of Pump Curve detects breaks and leakage

The feature detects breaks and leakage. End of curve triggers an alarm, shuts off the pump, or performs another programmed action


whenever a pump is found running at full speed without creating the desired pressure – a situation that can arise when a pipe breaks or leakage occurs.



Check Valve Ramp

The Check Valve Ramp prevents water hammering as the pump stops and the check valve closes.

The Check Valve Ramp slowly ramps down the pump speed around the value where the check valve ball is about to shut.



Dry Run Detection lowers maintenance costs


The VLT® AQUA Drive constantly evaluates the condition of the pump, based on internal frequency/power measurements.

In case of a too low power consumption – indicating a no or low flow situation – the VLT® AQUA Drive will stop.

Sleep Mode


Sleep Mode keeps pump wear and power consumption to an absolute minimum. In low flow situations, the pump will boost the system pressure and then stop.

Monitoring the pressure, the VLT® AQUA Drive will restart when the pressure falls below the required level.



Flow compensation

The flow compensation feature in VLT® AQUA Drive exploits the fact that flow resistance decreases with reduced flow. The pressure set point is accordingly reduced – which saves energy.



Initial/Final Ramp

The initial ramp provides fast acceleration of pumps to minimum speed, from where the normal ramp takes over. This prevents damage to the thrust bearings on the pump.

The final ramp decelerates pumps from min. speed to stop.

Payback time indication

One of the major reasons for applying a VLT® drive is the very short payback time due to energy savings. The VLT® AQUA drive comes with a unique feature which continuously shows the remaining payback time for the investment.

Motor Alternation

This built-in logic controls alternation between two pumps in duty/stand-by applications. Motion of the stand-by pump prevents sticking of the pump. An internal timer assures equal usage of the pumps.

With an option card it is possible to control alternations between 8 pumps.

AQUA users participated in developing the user interface

1 Graphical display

- International letters and signs
- Graphical display with bar-charts
- Easy overview
- Possible to select 27 languages
- iF awarded design

2 Menu structure

- Based on the well known matrix-system in today's VLT® drives
- Easy shortcuts for the experienced user
- Edit and operate in different set-ups simultaneously

3 Other benefits

- Removable during operation
- Up- and download functionality
- IP 65 rating when mounted in a panel door
- Up to 5 different variables visible at a time



4 Illumination

- Relevant buttons are illuminated when active

5 Quick Menus

- A Danfoss defined Quick Menu
- A personal defined Quick Menu
- A Changes Made menu lists the parameters unique to your application
- A Function Setup menu provides quick and easy set-up for specific applications
- A Logging menu provides access to operation history

6 Intuitive functions

- Info ("on board manual")
- Cancel ("undo")
- Alarm log (quick access)

iF The VLT® AQUA Drive has an award-winning Local Control Panel and a well structured menu system that ensures fast commissioning and trouble-free operation of the many powerful functions.
design award
winner
2004

VLT® Low Harmonic Drives

Danfoss Low Harmonic Drives offer well known features while reducing strain on the power grid.

Where the performance of other low harmonic technologies depends on the stability of the grid and load or affects the controlled motor, the new Danfoss VLT® Low Harmonic Drive continuously regulates the network and load conditions without affecting the connected motor.

VLT® Low Harmonic Drive are motor friendly, with output impulse & shaft voltages compatible with motors conforming to IEC 60034-17/25 & NEMA-MG1-1998 part 31.4.4.2), as per standard VLT® Drives.

The VLT® Low Harmonic Drive has the same modular build-up as Danfoss' standard high power drives and

shares similar features: high energy efficiency, back-channel cooling and user-friendly operation.

The VLT® Low Harmonic Drive meets the toughest harmonic recommendations and gives the user full readout of the unit performance with regard to the grid, including a graphical overview of grid behavior.

The perfect solution for

- Meeting the toughest harmonics recommendations/standards
- Generator-powered installations
- Installations with generator backup
- Soft power grids
- Installation of drives in grids with limited excess power capacity



Voltage range

- 380 – 480 V AC 50 – 60 Hz

Power Range

132 – 630 kW High Overload/
160 – 710 kW Normal Overload
(Matching drive frames D, E and F)

Enclosure degree

- IP 21 / NEMA 1, IP 54 hybrid

Specifications

Mains supply (L1, L2, L3)

Supply voltage	1 or 3 x 200 – 240 V ±10% 1 or 3 x 380 – 480 V ±10% 3 x 525 – 600 V ±10% 3 x 525 – 690 V ±10%
Supply frequency	50/60 Hz
True power factor (λ)	≥ 0.9
Switching on input supply L1, L2, L3	1-2 times/min.

Output data (U, V, W)

Output voltage	0 – 100% of supply voltage
Switching on output	Unlimited
Ramp times	1 – 3600 sec
Closed loop	0 – 132 Hz

VLT® AQUA Drive can provide 110% current for 1 minute.
Higher overload rating is achieved by oversizing the drive.

Digital inputs

Programmable digital inputs	6*
Logic	PNP or NPN
Voltage level	0–24 V
Thermistor inputs	1

*2 can be used as digital outputs

Analog input

Analog inputs	2
Modes	Voltage or current
Voltage level	0 – 10 V (scaleable)
Current level	0/4 – 20 mA (scaleable)

Pulse inputs

Programmable pulse inputs	2
Voltage level	0-24 VDC (PNP positive logic)
Pulse input accuracy	(0.1 – 110 kHz)
Utilize some of the digital inputs	

Analog output

Programmable analog outputs	1
Current range at analog output	0/4 – 20 mA
Max. load (24 V)	130 mA

Relay outputs

Programmable relay outputs (240 VAC, 2 A and 400 VAC, 2 A)	2
---	---

Fieldbus communication

Standard built in: FC Protocol Modbus RTU	Optional: PROFIBUS DeviceNet EtherNet/IP Modbus TCP IP PROFINET
---	--

Temperature

Ambient temperature	Up to 55° C
---------------------	-------------

Application options

A wide range of integrated water application options can be fitted into the drive:

- **Real time clock with battery back-up**
- **General purpose I/O option:**
3 digital inputs, 2 digital outputs, 1 analog current output, 2 analog voltage inputs
- **Relay option/cascade controller option:**
3 relay outputs
- **External 24 VDC supply option:**
24 VDC external supply can be connected to supply control and option cards
- **Brake chopper option:**
Connected to an external brake resistor, the brake chopper limits the load on the intermediate circuit in case the motor acts as generator.
- **Extended cascade control of up to a total of 6 pumps**
- **Advanced cascade control of up to a total of 9 pumps**
- **Analogue sensor input option with up to 3 temperature sensor inputs**

Power options

Danfoss Drives offers a wide range of external power options for use together with our drive in critical networks or applications:

- **Advanced Harmonic Filters:** for applications where reducing harmonic distortion is critical
- **dU/dt filters:** For providing motor isolation protection
- **Sine filters (LC filters):** For noiseless motor

Complementary products

- A broad range of soft starters
- Decentral drive solutions

PC software

- **MCT 10**
Ideal for commissioning and servicing the drive including guided programming of cascade controller, real time clock, smart logic controller and preventive maintenance. The software is available for free on www.danfoss.com
- **VLT® Energy Box**
Comprehensive energy analysis tool, shows the drive payback time
- **MCT 31**
Harmonics calculations tool

Sales and Service Contacts worldwide

Find your local expert team on www.danfoss.com/drives

- 24/7 availability
- Local service organisation is present in more than 100 countries – ready to support whenever and wherever you need, around the clock, 7 days a week.



Global Marine

Power, currents and enclosures ratings

FC 202	kW	T2 200 – 240 V								T4 380 – 480 V								T6 525 – 600 V					T7 525 – 690 V				
		1 ph				3 ph				1 ph				3 ph				A					A.				
		Amp.	IP 20			IP 21			IP 66	Amp.			Amp.			Amp.			A			A			A		
			≤440 V	>440 V	All IP cl*	≤440 V	>440 V	All IP cl*		≤440 V	>440 V	All IP cl*	≤440 V	>440 V	All IP cl*	≤440 V	>440 V	All IP cl*	≤550 V	>550 V	All IP cl*	≤550 V	>550 V	All IP cl*	550 V	690 V	All IP cl*
PK25	0.25	1.8																									
PK37	0.37	2.4																									
PK55	0.55	3.5																									
PK75	0.75	4.6																									
P1K1	1.1	6.6	A3	A5	A5	A2	A2	A5	A5										1.8	1.7							
P1K5	1.5	7.5																	2.9	2.7	A3	A3	A5	A5			
P2K2	2.2	10.6																	4.1	3.9							
P3K0	3	12.5																	5.2	4.9							
P3K7	3.7	16.7																									
P4K0	4.0																		6.4	6.1							
P5K5	5.5	24.2																	9.5	9	A3	A3	A5	A5			
P7K5	7.5	30.8																	11.5	11							
P11K	11	46.2																	19	18							
P15K	15	59.4																	23	22	B3	B1	B1	B1			
P18K	18	74.8																	28	27							
P22K	22	88																	36	34							
P30K	30	115																	43	41	B4	B2	B2	B2			
P37K	37	143																	54	52							
P45K	45	170																	65	62	C3	C1	C1	C1	54	52	
P55K	55																		87	83					65	62	
P75K	75																		105	83	C4	C2	C2	C2	87	83	
P90K	90																		137	131					105	100	D3 D1 D1
P110	110																								137	131	
P132	132																								162	155	
P160	160																								201	192	
P200	200																								253	242	D4 D2 D2
P250	250																								303	290	
P315	315																								360	344	
P355	355																										
P400	400																								418	400	D4 D2 D2
P450	450																								470	450	
P500	500																								523	500	E2 E1 E1
P560	560																								596	570	
P630	630																								630	630	
P710	710																								763	730	
P800	800																								889	850	F1/F3 F1/F3
P900	900																								988	945	
P1M0	1000																								1108	1060	F2/F4 F2/F4
P1M2	1200																								1317	1260	
P1M4	1400																								1479	1415	

F3 is a F1 frame with options cabinet; F4 is a F2 frame with options cabinet

IP 00/Chassis	IP 20/Chassis	IP 21/NEMA Type 1	With upgrade kit**	IP 54/NEMA Type 12	IP 55/NEMA Type 12	IP 66/NEMA Type 4X
---------------	---------------	-------------------	--------------------	--------------------	--------------------	--------------------


* Available in all IP classes. ** MCF 101 – IP 21 upgrade kit

Dimensions [mm]

	A2	A3	A5	B1	B2	B3	B4	C1	C2	C3	C4	D1	D2	D3	D4
H	268		420	480	650	399	520	680	770	550	660	1209	1589	1046	1327
W	90	130		242		165	230	308	370	308	370	420		408	
D	205		200	260		249	242	310	335	333		380		375	
H+	375					475	670			755	950				
W+	90	130				165	255			329	391				

H and W dimensions are with back-plate. H+ and W+ are with IP upgrade kit. D dimensions are without option A/B.

The numbers represent the terminals on the drive



This diagram shows a typical installation of the VLT® AQUA Drive. Power is connected to the terminals 91 (L1), 92 (L2) and 93 (L3) and the motor is connected to 96 (U), 97 (V) and 98 (W).

Terminals 88 and 89 are used for load sharing between drives.
Analogue inputs can be connected to

the 53 (V or mA), 54 (V or mA) terminals.

These inputs can be set up to either reference, feedback or thermistor. There are 6 digital inputs to be connected to terminals 18, 19, 27, 29, 32, and 33. Two digital input/output terminals (27 and 29) can be set up

as digital outputs to show an actual status or warning. The terminal 42 analogue output can show process values such as $0 - I_{\max}$.

On the 68 (P+) and 69 (N-) terminals' RS 485 interface, the drive can be controlled and monitored via serial communication.

Proven AQUA Experience – world wide



Freshwater supply for the city Novi Sad, Serbia
In the city of Novi Sad in Serbia, Danfoss Drives has installed 5 x 315 kW VLT® AQUA Drives in JKP Vodovod. The company JKP Vodovod is using water from the Danube River and after purification it is provided to people of Novi Sad and local area which counts around 350,000 inhabitants. Before investments they used an old regulation with valves and there was no central monitoring of the water system. Poor regulation and high maintenance costs have forced local management for investments. Now they have seen huge savings in electrical energy, even within a short period of usage.



VLT® drives make 70 billion litres of Sydney's wastewater drinkable
Authorities in Australia hope to recycle 70 billion litres of Sydney's wastewater every year by 2015 – and Danfoss is playing a key role in helping them hit this ambitious target. Danfoss Drives will deliver 11 x 200 – 400 kW High Power drives and AHF filters for the Western Sydney Replacement Flows Project. The Aus \$250 million project is Sydney's largest water recycling scheme and is a key part of the state's Metropolitan Water Plan.



Changi Water Reclamation Plant, Singapore
The Changi Water Reclamation plant is the cornerstone of the first phase of the Singapore Deep Tunnel Sewerage System. The plant is to replace six existing water reclamation plants in the long term. Danfoss VLT® drives and AHF filters were supplied for chemical and carbon scrubbers for the odour control, sedimentation tanks, bio-reactors, sedimentation tanks and solids building.



Perth Seawater Desalination Plant, Australia
VLT® drives and soft starters were chosen to run pumps when The Water Corporation of Western Australia – one of Australia's largest and most successful water service providers – invested \$387 million Australian dollars in Perth Seawater Desalination Plant – the largest of its type in the Southern Hemisphere. The company provides water and wastewater services to the burgeoning city of Perth and hundreds of towns and communities spread over 2.5 million square kilometres.



Wastewater Pumping in Cartagena, Colombia
Huge energy savings and a significant carbon reduction were achieved in the preliminary water treatment stage, where solids are separated from the sewage inflow. By applying Danfoss VLT® AQUA Drives to control the levels in the holding tanks, variable speed operation of the 4 x 370 kW pumps realised a return on investment within 6 months, and ongoing energy and carbon savings for the future. The additional operation result is a more constant flow through the subsequent processes, improving overall process efficiency.



Xi'an No.3 Waste Water treatment, China
Danfoss provided VLT® AQUA drives and MCD soft starters for Xi'an No.3 Wastewater treatment plant. It is one of three bundles of a retrofit project to improve the environment in Xi'an City of Shanxi province, China. The treatment capacity is 100,000 tons of sewage and 50,000 tons of recycled water per day.



Athens Wastewater Treatment Plant, Greece
VLT® drives up to 315 kW handle wastewater from a population of 5 million in Athens. VLT® operation saves approx. 25% energy. The Psytalia Wastewater Treatment Plant treats daily 750,000 m³ of sewage and has a nominal daily capacity of 1,000,000 m³.



Vienna's Main Sewage Treatment Plant, Austria
At Vienna's lowest point, where the Danube Canal meets the Danube, lies Vienna's Main Sewage Treatment Plant. Here around 90% of Vienna's wastewaters is purified. VLT® drives were chosen to operate the pumps that handle more than 500,000 cubic metres per day, which corresponds to a flow of a medium-size river.



Izmir Geothermal District Heating System, Turkey
VLT® drives operate the deep well and supply pumps in Izmir geothermal district heating. Applying VLT® drives leads to a very low electricity cost.

1 x 200 – 240 VAC and 1 x 380 – 480 VAC

1 x 200 – 240 VAC

Enclosure	IP 20 /Chassis		A3								
	IP 55 + IP 66 /NEMA 12		A5	B1					B2	C1	C2
			P1K1	P1K5	P2K2	P3K0	P3K7	P5K5	P7K5	P15K0	P22K0
Typical Shaft Output		[kW]	1.1	1.5	2.2	3	3.7	5.5	7.5	15	22
Typical Shaft Output at 240 V		[HP]	1.5	2.0	2.9	4.0	4.9	7.5	10	20	30
Output Current (1 x 200 – 240 V)	Continuous	[A]	6.6	7.5	10.6	12.5	16.7	24	30.8	59.4	88
	Intermittent	[A]	7.3	8.3	11.7	13.8	18.4	26.6	33.4	65.3	96.8
Output Power (208 V AC)	Continuous	[kVA]						5.00	6.40	12.27	18.30
Max. cable size (Mains, motor, brake)		[mm²] ([AWG])	0.2-4/4-10					10/7	35/2	50/1/0	95/4/0
Max. Input Current (1 x 200 – 240 V)	Continuous	[A]	12.5	15	20.5	24	32	46	59	111	172
	Intermittent	[A]	13.8	16.5	22.6	26.4	35.2	50.6	64	122	189.2
Max. pre-fuses		[A]	20	30	40		60	80	100	150	200
Environment											
Estimated power loss at rated max. load		[W]	44	30	44	60	74	110	150	300	440
Weight											
IP 20		[kg]	4.9								
IP 21		[kg]		23					27	45	65
IP 55, IP 66		[kg]		23					27	45	65
Efficiency			0.968	0.98							

1 x 380 – 480 VAC

Enclosure	IP 20 (IP 21*)/Chassis		B1		B2	C1	C2
	IP 21/NEMA 1, IP 55 + IP 66/NEMA 12						
			P7K5	P11K	P18K	P37K	
Typical Shaft Output		[kW]	7.5	11	18.5	37	
Typical Shaft Output at 460 V		[HP]	10	15	25	50	
Output Current (1 x 380 – 440 V)	Continuous	[A]	33	48	78	151	
	Intermittent	[A]	36	53	85.8	166	
Output Current (1 x 441 – 480 V)	Continuous	[A]	30	41	72	135	
	Intermittent	[A]	33	46	79.2	148	
Output Power (208 V AC)	Continuous	[kVA]	11.1	16.6	26.9	51.5	
Max. cable size Mains, motor, brake		[mm ²] ([AWG])	10/7	35/2	50/1/0	120/4/0	
Max. Input Current (1 x 380 – 440 V)	Continuous	[A]	33	48	78	151	
	Intermittent		36	53	85.8	166	
Max. Input Current (1 x 441 – 480 V)	Continuous	[A]	30	41	72	135	
	Intermittent		33	46	79.2	148	
Max. pre-fuses		[A]	63	80	160	250	
Environment							
Estimated power loss at rated max. load		[W]	300	440	740	1480	
Weight							
IP 20, IP 21, IP 55, IP 66		[kg]	23	27	45	65	
Efficiency			0.96				

3 x 200 – 240 VAC

Enclosure	IP 20 (IP 21*)/Chassis		A2						A3		
	IP 55 + IP 66 /NEMA 12		A5								
			PK25	PK37	PK55	PK75	P1K1	P1K5	P2K2	P3K0	P3K7
Typical Shaft Output		[kW]	0.25	0.37	0.55	0.75	1.1	1.5	2.2	3	3.7
Typical Shaft Output at 208 V		[HP]	0.25	0.37	0.55	0.75	1.5	2.0	2.9	4.0	4.9
Output Current (3 x 200 – 240 V)	Continuous	[A]	1.8	2.4	3.5	4.6	6.6	7.5	10.6	12.5	16.7
	Intermittent	[A]	1.98	2.64	3.85	5.06	7.3	8.3	11.7	13.8	18.4
Output Power (208 V AC)	Continuous	[kVA]	0.65	0.86	1.26	1.66	2.38	2.70	3.82	4.50	6.00
Max. cable size (Mains, motor, brake)		[mm²] ([AWG])	4 (10)								
Max. Input Current (3 x 200 – 240 V)	Continuous	[A]	1.6	2.2	3.2	4.1	5.9	6.8	9.5	11.3	15.0
	Intermittent	[A]	1.7	2.42	3.52	4.51	6.5	7.5	10.5	12.4	16.5
Max. pre-fuses		[A]	10				20			32	
Environment											
Estimated power loss at rated max. load		[W]	21	29	42	54	63	82	116	155	185
Weight											
IP 20		[kg]	4.9							6.6	
IP 21		[kg]	5.5							7.5	
IP 55, IP 66		[kg]	13.5								
Efficiency			94		95		0.96				

Enclosure	IP 20 (IP 21*)/Chassis		B3			B4		C3		C4	
	IP 21/NEMA 1, IP 55 + IP 66/NEMA 12		B1			B2	C1		C2		
			P5K5	P7K5	P11K	P15K	P18K	P22K	P30K	P37K	P45K
Typical Shaft Output		[kW]	5.5	7.5	11	15	18.5	22	30	37	45
Typical Shaft Output at 208 V		[HP]	7.5	10	15	20	25	30	40	50	60
Output Current (3 x 200 – 240 V)	Continuous	[A]	24.2	30.8	46.2	59.4	74.8	88.0	115	143	170
	Intermittent	[A]	26.6	33.9	50.8	65.3	82.3	96.8	127	157	187
Output Power (208 V AC)	Continuous	[kVA]	8.7	11.1	16.6	21.4	26.9	31.7	41.4	51.5	61.2
Max. cable size Mains, motor, brake		[mm ²] ([AWG])	10 (7)			35 (2)	50 (1/0) (B4 = 35 (2))			95 (4/0)	120 (250 MCM)
Max. cable size mains With mains disconnect switch included		[mm ²] ([AWG])	16 (6)			35 (2)			70 (3/0)	185 (kcmil 350)	
Max. Input Current (3 x 200 – 240 V)	Continuous	[A]	22.0	28.0	42.0	54.0	68.0	80.0	104.0	130.0	154.0
	Intermittent		24.2	30.8	46.2	59.4	74.8	88.0	114.0	143.0	169.0
Max. pre-fuses		[A]	63	63	63	80	125	125	160	200	250
Environment											
Estimated power loss at rated max. load		[W]	269	310	447	602	737	845	1140	1353	1636
Weight											
IP 20		[kg]	12			23.5		35		50	
IP 21, IP 55, IP 66		[kg]	23			27	45			65	
Efficiency			0.96					0.97			

* (A2, A3, B3, B4, C3 and C4 may be converted to IP21 using a conversion kit.
(Please see also items Mechanical mounting in Operating Instructions and IP 21/ Type 1 Enclosure kit in the Design Guide.))

380 – 480 VAC

Enclosure		IP 20 (IP 21*)/Chassis	A2					A3	
		IP 55 + IP 66 /NEMA 12	A5						
			P1K1	P1K5	P2K2	P3K0	P4K0	P5K5	P7K5
Typical Shaft Output		[kW]	1.1	1.5	2.2	3	4	5.5	7.5
Typical Shaft Output at 460 V		[HP]	1.5	2.0	2.9	4.0	5.0	7.5	10
Output Current (3 x 380 – 440 V)	Continuous	[A]	3	4.1	5.6	7.2	110	13	16
	Intermittent	[A]	3.3	4.5	6.2	7.9	11	14.3	17.6
Output Current (3 x 441 – 480 V)	Continuous	[A]	2.7	3.4	4.8	6.3	8.2	11	14.5
	Intermittent	[A]	3.0	3.7	5.3	6.9	9.0	12.1	15.4
Output Power (400 V AC)	Continuous	[kVA]	2.1	2.8	3.9	5.0	6.9	9.0	11.0
Output Power (460 V AC)	Continuous	[kVA]	2.4	2.7	3.8	5.0	6.5	8.8	11.6
Max. cable size (Mains, motor, brake)		[mm ²] ([AWG])	4 (10)						
Max. Input Current (3 x 380 – 440 V)	Continuous	[A]	2.7	3.7	5.0	6.5	9.0	11.7	14.4
	Intermittent	[A]	3.0	4.1	5.5	7.2	9.9	12.9	15.8
Max. Input Current (3 x 441 – 480 V)	Continuous	[A]	2.7	3.1	4.3	5.7	7.4	9.9	13.0
	Intermittent	[A]	3.0	3.4	4.7	6.3	8.1	10.9	14.3
Max. pre-fuses		[A]	10	10	20	20	20	32	32
Environment									
Estimated power loss at rated max. load		[W]	58	62	88	116	124	187	255
Weight									
IP 20		[kg]	4.8	4.9				6.6	
IP 55, IP 66		[kg]	13.5					14.2	
Efficiency			0.96	0.97					

Enclosure		IP 20 (IP 21*)/Chassis	B3			B4			C3			C4	
		IP 21/NEMA 1, IP 55 + IP 66/NEMA 12	B1			B2		C1			C2		
			P11K	P15K	P18K	P22K	P30K	P37K	P45K	P55K	P75K	P90K	
Typical Shaft Output		[kW]	11	15	18.5	22	30	37	45	55	75	90	
Typical Shaft Output at 460 V		[HP]	15	20	25	30	40	50	60	75	100	125	
Output Current (3 x 380 – 439 V)	Continuous	[A]	24	32	37.5	44	61	73	90	106	147	177	
	Intermittent	[A]	26.4	35.2	41.3	48.4	67.1	80.3	99	117	162	195	
Output Current (3 x 440 – 480 V)	Continuous	[A]	21	27	34	40	52	65	80	105	130	160	
	Intermittent	[A]	23.1	29.7	37.4	44	61.6	71.5	88	116	143	176	
Output Power (400 V AC)	Continuous	[kVA]	16.6	22.2	26	30.5	42.3	50.6	62.4	73.4	102	123	
Output Power (460 V AC)	Continuous	[kVA]	16.7	21.5	27.1	31.9	41.4	51.8	63.7	83.7	104	128	
Max. cable size Mains, motor, brake		[mm ²] ([AWG])	10 (7)			35 (2)		50 (1/0) (B4 = 35 (2))			95 (4/0)	120 (250 MCM) ¹⁾	
Max. cable size mains With mains disconnect switch included		[mm ²] ([AWG])	16 (6)					35 (2)			70 (3/0)	185 (kcmil 350)	
Max. Input Current (3 x 380 – 439 V)	Continuous	[A]	22	29	34	40	55	66	82	96	133	161	
	Intermittent		24.2	31.9	37.4	44	60.5	72.6	90.2	106	146	177	
Max. Input Current (3 x 440 – 480 V)	Continuous	[A]	19	25	31	36	47	59	73	95	118	145	
	Intermittent		20.9	27.5	34.1	39.6	51.7	64.9	80.3	105	130	160	
Max. pre-fuses		[A]	63	63	63	63	80	100	125	160	250	250	
Environment													
Estimated power loss at rated max. load		[W]	278	392	465	525	698	739	843	1083	1384	1474	
Weight													
IP 20		[kg]	12			23.5			35		50		
IP 21, IP 55, IP 66		[kg]	23			27		45			65		
Efficiency			0.98									0.99	

* (A2, A3, B3, B4, C3 and C4 may be converted to IP21 using a conversion kit. Please contact Danfoss.
(Please see also items Mechanical mounting in Operating Instructions and IP 21/ Type 1 Enclosure kit in the Design Guide.))
1) With brake and load sharing 95 (4/0)

380 – 480 VAC

Enclosure		IP 21, IP 54		D1		D2		
		IP 00		D3		D4		
				P110	P132	P160	P200	P250
Typical Shaft Output at 400 V		[kW]	110	132	160	200	250	
Typical Shaft Output at 460 V		[HP]	150	200	250	300	350	
Output Current								
Continuous (3 x 380 – 400 V)		[A]	212	260	315	395	480	
Intermittent (3 x 380 – 400 V)		[A]	233	286	347	435	528	
Continuous (3 x 441 – 480 V)		[A]	190	240	302	361	443	
Intermittent (3 x 441 – 480 V)		[A]	209	264	332	397	487	
Output Power								
Continuous (400 VAC)		[kVA]	147	180	218	274	333	
Continuous (460 VAC)		[kVA]	151	191	241	288	353	
Max. Input Current								
Continuous (3 x 380 – 400 V)		[A]	204	251	304	381	463	
Continuous (3 x 441 – 480 V)		[A]	183	231	291	348	427	
Max. cable size Mains motor, brake and load share		[mm²] ([AWG])	2 x 70 (2 x 2/0)		2 x 150 (2 x 300 mcm)			
Max. external pre-fuses		[A]	300	350	400	500	630	
Estimated power loss at rated max. load – 400 V		[W]	2907	3358	3915	4812	5517	
Estimated power loss at rated max. load – 460 V		[W]	2600	3079	3781	4535	5024	
Weight	IP 21, IP 54	[kg]	96	104	125	136	151	
	IP 00	[kg]	82	91	112	123	138	
Efficiency			0.98					
Output Frequency			[Hz]	0 – 800				

Enclosure	IP 21, IP 54		E1				F1/F3				F2/F4	
	IP 00		E2									
			P315	P355	P400	P450	P500	P560	P630	P710	P800	P1M0
Typical Shaft Output at 400 V		[kW]	315	355	400	450	500	560	630	710	800	1000
Typical Shaft Output at 460 V		[HP]	450	500	550/600	600	700	750	900	1000	1200	1350
Output Current												
Continuous (3 x 380 – 400 V)		[A]	600	658	745	800	880	990	1120	1260	1460	1720
Intermittent (3 x 380 – 400 V)		[A]	660	724	820	880	968	1089	1232	1386	1606	1892
Continuous (3 x 441 – 480 V)		[A]	540	590	678	730	780	890	1050	1160	1380	1530
Intermittent (3 x 441 – 480 V)		[A]	594	649	746	803	858	979	1155	1276	1518	1683
Output Power												
Continuous (at 400 V)		[kVA]	416	456	516	554	610	686	776	873	1012	1192
Continuous (at 460 V)		[kVA]	430	4770	540	582	621	709	837	924	1100	1219
Max. Input Current												
Continuous (3 x 380 – 400 V)		[A]	590	647	733	787	857	964	1090	1227	1422	1675
Continuous (3 x 441 – 480 V)		[A]	531	580	667	718	759	867	1022	1129	1344	1490
Max. cable size Motor		[mm ²] ([AWG])	4 x 240 (3 x 500 mcm)				8 x 150 (8 x 300 mcm)				12 x 150 (12 x 300 mcm)	
Max. cable size Mains		[mm ²] ([AWG])					8 x 240 (8 x 500 mcm)					
Max. cable size Loadsharing		[mm ²] ([AWG])					4 x 120 (4 x 250 mcm)					
Max. cable size Brake		[mm ²] ([AWG])	1 x 185 (2 x 350 mcm)				4 x 185 (4 x 350 mcm)				6 x 185 (6 x 350 mcm)	
Max. external pre-fuses		[A]	700	900			1600		2000		2500	
Estimated power loss at rated max. load – 400 V		[W]	6706	7532	8677	9473	10161	11822	12514	14671	17294	19280
Estimated power loss at rated max. load – 460 V		[W]	5930	6725	7820	8527	8877	10424	11595	13215	16228	16625
Weight	IP 54	[kg]	263	270	272	313	1299				1541	
	IP 21	[kg]					1004				1246	
	IP 00	[kg]					–					
Efficiency			0.98									
Output Frequency		[Hz]	0 – 800									

525 – 690 VAC

Enclosure																		
IP 20 Chassis		A3							B3			B4		C3		C4		
IP 21/NEMA 1									B1			B2		C1		C2		
IP 55, IP 66/NEMA 12		A5																
		P1K1	P1K5	P2K2	P3K0	P4K0	P5K5	P7K5	P11K	P15K	P18K	P22K	P30K	P37K	P45K	P55K	P75K	P90K
Typical Shaft Output	[kW]	1.1	1.5	2.2	3	4	5.5	7.5	11	15	18.5	22	30	37	45	55	75	90
Output Current																		
Continuous (3 x 525 – 550 V)	[A]	2.6	2.9	4.1	5.2	6.4	9.5	11.5	19	23	28	36	43	54	65	87	105	137
Intermittent (3 x 525 – 550 V)	[A]	2.9	3.2	4.5	5.7	7.0	10.5	12.7	21	25	31	40	47	59	72	96	116	151
Continuous (3 x 525 – 600 V)	[A]	2.4	2.7	3.9	4.9	6.1	9.0	11.0	18	22	27	34	41	52	62	83	100	131
Intermittent (3 x 525 – 600 V)	[A]	2.6	3.0	4.3	5.4	6.7	9.9	12.1	20	24	30	37	45	57	68	91	110	144
Output Power																		
Continuous (525 V AC)	[kVA]	2.5	2.8	3.9	5.0	6.1	9.0	11.0	18.1	21.9	26.7	34.3	41	51.4	61.9	82.9	100	130.5
Continuous (575 V AC)	[kVA]	2.4	2.7	3.9	4.9	6.1	9.0	11.0	17.9	21.9	26.9	33.9	40.8	51.8	61.7	82.7	99.6	130.5
Max. cable size IP 21/55/66 (mains, motor, brake)	[mm ²] ([AWG])	4 (10)							10 (7)			35 (2)		50 (1/0)		95 (4/0)	120 (250 MCM)	
Max. cable size IP 20 (mains, motor, brake)	[mm ²] ([AWG])	4 (10)							10 (7)			35 (2)		50 (1/0)		95 (4/0)	150 (250 MCM) ¹⁾	
Max. cable size mains With mains disconnect switch included	[mm ²] ([AWG])	4 (10)							16 (6)				35 (2)			70 (3/0)	185 (kcmil 350)	
Max. Input Current																		
Continuous (3 x 525 – 600 V)	[A]	2.4	2.7	4.1	5.2	5.8	8.6	10.4	17.2	20.9	25.4	32.7	39	49	59	78.9	95.3	124.3
Intermittent (3 x 525 – 600 V)	[A]	2.7	3.0	4.5	5.7	6.4	9.5	11.5	19	23	28	36	43	54	65	87	105	137
Max. pre-fuses	[A]	10		20			32		63				80	100	125	160	250	250
Environment																		
Estimated power loss at rated max. load	[W]	50	65	92	122	145	195	261	300	400	475	525	700	750	850	1100	1400	1500
Weight																		
IP 20	[kg]	6.5					6.6		12			23.5		35		50		
IP 21, IP 55, IP 66	[kg]	13.5					14.2		23			27		45		65		
Efficiency		0.97							0.98									

1) With brake and load sharing 95 (4/0)

525 – 690 VAC

Enclosure	IP 21, IP 54		D1						D2		
	IP 00		D3						D4		
			P45K	P55K	P75K	P90K	P110	P132	P160	P200	P250
Typical Shaft Output at 550 V		[kW]	37	45	55	75	90	110	132	160	200
Typical Shaft Output at 575 V		[HP]	50	60	75	100	125	150	200	250	300
Typical Shaft Output at 690 V		[kW]	45	55	75	90	110	132	160	200	250
Output Current											
Continuous (at 3 x 525 – 550 V)		[A]	56	76	90	113	137				
Continuous (at 550 V)		[A]						162	201	253	303
Intermittent (60 sec overload) (at 550 V)		[A]	62	84	99	124	151	178	221	278	333
Continuous (at 3 x 551 – 690 V)		[A]	54	73	86	108	131				
Continuous (at 575/690 V)		[A]						155	192	242	290
Intermittent (60 sec overload) (at 575/690 V)		[A]	59	80	95	119	144	171	211	266	319
Output Power											
Continuous (at 550 V)		[kVA]	53	72	86	108	131	154	191	241	289
Continuous (at 575 V)		[kVA]	54	73	86	108	130	154	191	241	289
Continuous (at 690 V)		[kVA]	65	87	103	129	157	185	229	289	347
Max. Input Current											
Continuous (at 550 V)		[A]	60	77	89	110	130	158	198	245	299
Continuous (at 575 V)		[A]	58	74	85	106	124	151	189	234	286
Continuous (at 690 V)		[A]	58	77	87	109	128	155	197	240	296
Max. cable size Mains, motor, load share and brake		[mm ²] ([AWG])	2 x 70 (2 x 2/0)					2 x 70 (2 x 2/0)		2 x 150 (2 x 300 mcm)	
Max. external pre-fuses		[A]	125	160	200	200	250	315	350	350	400
Estimated power loss at rated max. load – 600 V		[W]	1398	1645	1827	2157	2533	2963	3430	4051	4867
Estimated power loss at rated max. load – 690 V		[W]	1458	1717	1913	2262	2662	3430	3612	4292	5156
Weight	IP 21, IP 54	[kg]	96						104	125	136
	IP 00	[kg]	82						91	112	123
Efficiency			0.97		0.98						
Output Frequency		[Hz]	0 – 600								


Enclosure		IP 54/NEMA 12		D2	E1				F1/F3 ¹⁾			F2/F4 ¹⁾			
		IP 21/NEMA 1													
		IP 00		D4		E2				–					
				P315	P400	P450	P500	P560	P630	P710	P800	P900	P1M0	P1M2	P1M4
Typical Shaft Output at 550 V		[kW]	250	315	355	400	450	500	560	670	750	850	1000	1100	
Typical Shaft Output at 575 V		[HP]	350	400	450	500	600	650	750	950	1050	1150	1350	1500	
Typical Shaft Output at 690 V		[kW]	315	400	450	500	560	630	710	800	900	1000	1200	1400	
Output Current															
Continuous (3 x 550 V)		[A]	360	418	470	523	596	630	763	889	988	1108	1317	1479	
Intermittent (3 x 550 V)		[A]	396	460	517	575	656	693	839	978	1087	1219	1449	1627	
Continuous (3 x 690 V)		[A]	344	400	450	500	570	630	730	850	945	1060	1260	1415	
Intermittent (3 x 690 V)		[A]	378	440	495	550	627	693	803	935	1040	1166	1386	1557	
Output Power															
Continuous (at 550 VAC)		[kVA]	343	398	448	498	568	600	727	847	941	1056	1255	1409	
Continuous (at 575 VAC)		[kVA]						627							
Continuous (at 690 VAC)		[kVA]	411	478	538	598	681	753	872	1016	1129	1267	1506	1691	
Max. Input Current															
Continuous (3 x 550 V)		[A]	355	408	453	504	574	607	743	866	962	1079	1282	1440	
Continuous (3 x 575 V)		[A]	339	390	434	482	549	607	711	828	920	1032	1227	1378	
Continuous (3 x 690 V)		[A]	352	400											
Max. cable size Mains		[mm²] ([AWG])	2 x 185 (2 x 300 mcm)	4 x 240 (4 x 500 mcm)				8 x 240 (8 x 500 mcm)							
Max. cable size Motor		[mm²] ([AWG])						8 x 150 (8 x 300 mcm)				12 x 150 (12 x 300 mcm)			
Max. cable size Brake		[mm²] ([AWG])						2 x 185 (2 x 350 mcm)				4 x 185 (4 x 350 mcm)			6 x 185 (6 x 350 mcm)
Max. mains pre-fuses		[A]	500	550	700		900		2000					2500	
Estimated power loss at rated max. load – 600 VAC		[W]	4308	4757	4974	5622	7018	7792	8933	10310	11692	12909	15358	17602	
Estimated power loss at rated max. load – 690 VAC		[W]	4486	4925	5128	5794	7221	8017	9212	10659	12080	13305	15865	18173	
Weight	IP 21, IP 54	[kg]	151	165	263		272	313	1004			1246		1280	
	IP 00	[kg]	138	151	221		236	277	–						
Efficiency			0.98												
Output Frequency		[Hz]	0 – 500												

1) Adding the F-enclosure option cabinet (resulting in the F3 and F4 enclosure sizes) adds 295 kg to the estimated weight.


Dimensions VLT® AQUA Drive

In mm

A2 Enclosures




A3 Enclosures




Dimensions VLT® AQUA Drive


In mm



A5 Enclosures



B1 Enclosures




B2 Enclosures


Dimensions VLT® AQUA Drive

In mm


B3 Enclosures



B4 Enclosures




C1 Enclosures



Dimensions VLT® AQUA Drive

In mm



C2 Enclosures




C3 Enclosures

C4 Enclosures

Dimensions VLT® AQUA Drive




In mm

D1 Enclosures (Floor- or cabinet Mount)



Optional pedestal 176F1827 available for stand-alone floor mount installations (adds 200 mm to height)

D2 Enclosures (Floor- or cabinet Mount)





Optional pedestal 176F1827 available for stand-alone floor mount installations (adds 200 mm to height)




Drives shown with optional disconnect switch

Dimensions VLT® AQUA Drive

In mm



D3 Enclosures (Cabinet Mount)




Drives shown with optional disconnect switch

D4 Enclosures (Cabinet Mount)


Dimensions VLT® AQUA Drive

In mm

E1 Enclosures (Floor Mount)





E2 Enclosures (Cabinet Mount)





Drives shown with optional disconnect switch

Dimensions VLT® AQUA Drive

In mm



F1 Enclosures (Floor Mount)





F2 Enclosures (Floor Mount)



Dimensions VLT® AQUA Drive

In mm

F3 Enclosures (Floor Mount)



F4 Enclosures (Floor Mount)



VLT® AQUA Drive Options



Typecode Position

VLT® PROFIBUS DP V1 MCA 101

- PROFIBUS DP V1 gives you wide compatibility, a high level of availability, support for all major PLC vendors, and compatibility with future versions
- Fast, efficient communication, transparent installation, advanced diagnosis and parameterisation and auto-configuration of process data via GSD-file
- A-cyclic parameterisation using PROFIBUS DP V1, PROFIdrive or Danfoss FC profile state machines, PROFIBUS DP V1, Master Class 1 and 2

Ordering number 130B1100 uncoated – 130B1200 coated (Class 3C3/IEC 60721-3-3)



13

VLT® DeviceNet MCA 104

- This modern communications model offers key capabilities that let you effectively determine what information is needed and when
- You will also benefit from ODVA's strong conformance testing policies, which ensure that products are interoperable

Ordering number 130B1102 uncoated – 130B1202 coated (Class 3C3/IEC 60721-3-3)



13

VLT® PROFINET RT MCA 120

The VLT® PROFINET Option offers connectivity to PROFINET based networks via the PROFINET Protocol. The option is able to handle a single connection with an Actual Packet Interval down to 1 ms in both directions, positioning it among the fastest performing PROFINET devices in the market.

- Built-in web server for remote diagnosis and reading out of basic drive parameters
- An e-mail notifiicator can be configured for sending an e-mail message to one or several receivers, if certain warnings or alarms occur, or have cleared again
- TCP/IP for easy access to Drive configuration data from MCT 10
- FTP (File Transfer Protocol) file up- and download
- Support of DCP (discovery and configuration protocol)



13

VLT® EtherNet IP MCA 121

EtherNet will become the future standard for communication at the factory floor. The EtherNet Option is based on the newest technology available for the Industrial use and handles even the most demanding requirements. EtherNet/IP extends commercial off-the-shelf EtherNet to the Common Industrial Protocol (CIP™) – the same upper-layer protocol and object model found in DeviceNet.

The VLT® MCA 121 offers advanced features as:

- Built-in high performance switch enabling line-topology, and eliminating the need for external switches
- Advanced switch and diagnoses functions
- Built-in web server
- E-mail client for service notification



13

VLT® Modbus TCP MCA 122


The VLT® Modbus Option offers connectivity to Modbus TCP based networks, such as Groupe Schneider PLC system via the Modbus TCP Protocol. The option is able to handle a single connection with an Actual Packet Interval down to 5 ms in both directions, positioning it among the fastest performing Modbus TCP devices in the market.

- Built-in web-server for remote diagnosis and reading out basic drive parameters
- An e-mail notifiicator can be configured for sending an e-mail message to one or several receivers, if certain warnings or alarms occur, or have cleared again
- Two Ethernet ports with built-in switch
- FTP (File Transfer Protocol) file up- and download
- Protocol – automatic – IP address configuration



13

VLT® AQUA Drive Options

Typecode Position		
14-B		VLT® General Purpose I/O MCB 101 The I/O option offers an extended number of control inputs and outputs. • 3 digital inputs 0-24 V: Logic '0' < 5 V; Logic '1' > 10V • 2 analogue inputs 0-10 V: Resolution 10 bit plus sign • 2 digital outputs NPN/PNP push pull • 1 analogue output 0/4-20 mA • Spring loaded connection • Separate parameter settings Ordering number 130B1125 uncoated – 130B1212 coated (Class 3C3/IEC 60721-3-3)
14-B		VLT® Relay Option MCB 105 Lets you extend relay functions with 3 additional relay outputs. Max. terminal load: • AC-1 Resistive load 240 V AC 2 A • AC-15 Inductive load @cos φ 0.4 240 V AC 0.2 A • DC-1 Resistive load 24 V DC 1 A • DC-13 Inductive load @cos φ 0.4 24 V DC 0.1 A Min. terminal load: • DC 5 V 10 mA • Max switch rate at rated load/min. load 6 min⁻¹/20 sec⁻¹ Ordering number 130B1110 uncoated – 130B1210 coated (Class 3C3/IEC 60721-3-3)
14-B		VLT® Analog I/O Option MCB 109 This analogue input/output option is easily fitted in the frequency converter for upgrading to advanced performance and control using the additional in/outputs. This option also upgrades the frequency converter with a battery back-up supply for the clock built into the frequency converter. This provides stable use of all frequency converter clock functions as timed actions etc. • 3 analogue inputs, each configurable as both voltage and temperature input • Connection of 0-10 V analogue signals as well as PT1000 and NI1000 temperature inputs • 3 analogue outputs each configurable as 0-10 V outputs • Incl. back-up supply for the standard clock function in the frequency converter The back-up battery typically lasts for 10 years, depending on environment. Ordering number 130B1143 uncoated – 130B1243 coated (Class 3C3/IEC 60721-3-3)
14-B		VLT® Sensor Input Option MCB 114 The option protects the motor from being overheated by monitoring the bearings and windings temperature in the motor. The limits as well as the action are adjustable and the individual sensor temperature is visible as a read out in the display or by field bus. • Protects the motor from overheating • Three self-detecting sensor inputs for 2 or 3 wire PT100/PT1000 sensors • One additional analogue input 4-20mA
14-B		VLT® Extended Cascade Controller MCO 101 Easily fitted and upgrades the built-in cascade controller to operate more pumps and more advanced pump control in master/follower mode. • Up to 6 pumps in standard cascade setup • Up to 6 pumps in master/follower setup • Technical specification: See MCB 105 Relay Option
16-C		VLT® Advanced Cascade Controller MCO 102 Easily fitted and upgrades the built-in cascade controller to operate up to 8 pumps and more advanced pump control in master/follower mode. The same cascade controller hardware goes for for the entire power range up to 1.2 MW. • Up to 9 pumps in standard cascade setup • Up to 8 pumps in master/follower setup

Installation of options is a matter of plug-and-play

VLT® AQUA Drive Options

		Typecode Position
VLT® 24 V DC Supply Option MCB 107 The option is used to connect an external DC supply to keep the control section and any installed option active when mains power is down. • Input voltage range 24 V DC +/- 15% (max. 37 V in 10 sec.) • Max. input current 2.2 A • Max. cable length 75 m • Input capacitance load < 10 µF • Power-up delay < 0.6 s • Easy to install in drives in existing machines • Keeps the control board and options active during power cuts • Keeps fieldbuses active during power cuts Ordering number 130B1108 uncoated – 130B1208 coated (Class 3C3/IEC 60721-3-3)		18
		Typecode Position
LCP 102 Graphical Local Control Panel • Multi-language display • Status messages • Quick Menu for easy commissioning • Parameter setting and explanation of parameter function • Adjustment of parameters • Full parameter backup and copy function • Alarm logging • Info button – explains the function of the selected item on display • Hand-operated start/stop, or automatic mode selection • Reset function • Trend graph Ordering number 130B1107		7
LCP 101 Numerical Local Control Panel The numerical control panel offers an excellent MMI interface to the drive. • Status messages • Quick menu for easy commissioning • Parameter setting and adjustment • Hand-operated start/stop function or automatic mode select • Reset function Ordering number 130B1124		7
LCP Panel Mounting Kit For easy installation of the LCP 101 and LCP 102 in e.g. a cabinet. • IP65 (front) • Thumb screws for tool-free installation • Incl. 3 meters of cables in industry quality (also available separately) • With or without LCP operating unit • Each time easy to install Ordering number 130B1117 (Mounting kit for all LCP's including fasteners, 3 m cable and gasket) Ordering number 130B1113 (Incl. graphical LCP, fasteners, 3 m cable and gasket) Ordering number 130B1114 (Incl. numerical LCP, fasteners and gasket) Ordering number 130B1129 (LCP front mounting IP55/IP66) – Ordering number 175Z0929 (cable only) Ordering number 130B1170 (Panel Mounting Kit for all LCP w.o. cable)		

Installation of options is a matter of plug-and-play

VLT® AQUA Drive Accessories



Profibus Adapter Sub-D9 Connector

The adapter makes linking of fieldbus connections pluggable. For use with option A.

- Option to use prefabricated Profibus cabling
- For retrofit

Ordering number 130B1112 for frame size A, B and C

Ordering number 176F1742 for frame D and E



Screw terminals

Screw terminals as an alternative to the standard springloaded terminals.

- Pluggable
- Terminal name is described

Ordering number 130B1116



IP 21/Type 12 (NEMA1) Kit

The IP 21/Type 12 (NEMA1) kit is used for installation of VLT® drives in dry environments.

The enclosure kits are available for frame sizes A1, A2, A3, B3, B4, C3 and C4

- Supports VLT® drives from 1.1 to 90 kW
- Used on standard VLT® drives with or without mounted option modules
- IP 41 on top side
- PG 16 and PG 21 holes for glands

130B1122 for frame size A2, 130B1123 for frame size A3, 130B1187 for frame size B3, 130B1189 for frame size B4, 130B1191 for frame size C3, 130B1193 for frame size C4



Kit for panel through mount

Mounting kit for external cooling of the heatsink for appliances with A5, B1, B2, C1 and C2 housing.

- The air conditioned installation space can be reduced.
- Additional cooling may be omitted
- No contamination of electronics by forced ventilation
- Facilitates integrated assembly
- Reduced cabinet depth/less space



VLT® Brake Resistors

Energy generated during braking is absorbed by the resistors, protecting electrical components from heating up. Danfoss brake resistors cover the full power range.

- Quick braking of heavy loads
- Braking energy is only absorbed into the brake resistor
- External mounting makes it possible to use the generated heat
- All necessary approvals are available



USB Extension

USB extension for IP 55 and IP 66 enclosures. Makes the USB connector available outside the drive. The USB extension is designed for mounting in a cable gland in the bottom of the drive, which makes PC communication very easy even in drives with high IP rating.

USB extension for A5-B1, D and E enclosures, 350 mm cable, ordering number 130B1155

USB extension for B2-C enclosures, 650 mm cable, ordering number 130B1156

USB extension for F enclosures, ordering number 176F1784

VLT® AQUA Drive Accessories



VLT® Harmonic Filter AHF 005/010 MCE

Easy, effective harmonic distortion reduction by connecting the AHF 005/010 harmonic filter in front of a Danfoss frequency converter.

- AHF 005 reduces total harmonic current distortion to 5%
- AHF 010 reduces total harmonic current distortion to 10%
- Small compact housing that can be fitted into a panel
- Easy to use in retrofit applications
- User-friendly start-up – no adjustment necessary
- No routine maintenance required



VLT® Sine-Wave Filters MCC 101

Sine-wave filters are placed between the frequency converter and the motor to optimise the motor power current. It provides a sinusoidal phase-to-phase motor voltage. The filters reduce motor insulation stress, acoustic noise from the motor, and bearing currents (especially in large motors).

- Reduces motor insulation stress
- Reduces acoustic noise from the motor
- Reduces bearing currents (especially in large motors)
- Enables use of longer motor cables
- Reduces losses in the motor
- Prolongs service lifetime
- IP 20 or IP 21



VLT® dU/dt filter MCC 102

VLT® dU/dt filters are placed between the frequency converter and the motor to eliminate very fast voltage changes. The motor terminal phase-to-phase voltage is still pulse shaped but its dU/dt values are reduced.

- These filters reduce stress on the motor's insulation and are recommended in applications with older motors, aggressive environments or frequent braking which cause increased DC link voltage.
- IP 20 or IP 21



SVCD – regenerative braking

Transferring the generated power from a decelerating motor back into the power supply enables braking of virtually unlimited duration.

- Energy efficient braking
- Self-synchronisation
- DC-DC coupling of multiple drives possible
- High efficiency through IGBT technology
- Simple operation
- Overload protection in regenerative operation





Environmentally responsible

VLT® products are manufactured with respect for the safety and well-being of people and the environment.

All activities are planned and performed taking into account the individual employee, the work environment and the external environment. Production takes place with a minimum of noise, smoke or other pollution and environmentally safe disposal of the products is pre-prepared.

UN Global Compact

Danfoss has signed the UN Global Compact on social and environmental responsibility and our companies act responsibly towards local societies.

EU Directives

All factories are certified according to ISO 14001 standard. All products fulfil the EU Directives for General Product Safety and the Machinery directive. Danfoss Drives is, in all product series, implementing the EU Directive concerning Hazardous Substances in Electrical and Electrical Equipment (RoHS) and is designing all new product series according to the EU Directive on Waste Electrical and Electronic Equipment (WEEE).

Impact on energy savings

One year's energy savings from our annual production of VLT® drives will save the energy equivalent to the energy production from a major power plant. Better process control at the same time improves product quality and reduces waste and wear on equipment.

What VLT® is all about

Danfoss Drives is the world leader among dedicated drives providers – and still gaining market share.

Dedicated to drives

Dedication has been a key word since 1968, when Danfoss introduced the world's first mass produced variable speed drive for AC motors – and named it VLT®.

Twenty five hundred employees develop, manufacture, sell and service drives and soft starters in more than one hundred countries, focused only on drives and soft starters.

Intelligent and innovative

Developers at Danfoss Drives have fully adopted modular principles in development as well as design, production and configuration.

Tomorrow's features are developed in parallel using dedicated technology platforms. This allows the development of all elements to take place in parallel, at the same time reducing time to market and ensuring that customers always enjoy the benefits of the latest features.

Rely on the experts

We take responsibility for every element of our products. The fact that we develop and produce our own features, hardware, software, power modules, printed circuit boards, and accessories is your guarantee of reliable products.

Local backup – globally

VLT® motor controllers are operating in applications all over the world and Danfoss Drives' experts located in more than 100 countries are ready to support our customers with application advice and service wherever they may be.

Danfoss Drives experts don't stop until the customer's drive challenges are solved.

